

general list of works for boiler change	tp	Cost	Total
<p>to attend site and install system cleaner and leave system running minimum 1 hour [if boiler will not run flushing will be done on drain down]</p> <p>to reattend site and drain down system</p> <p>to disconnect boiler and label pipe work , label control cables</p> <p>to purchase 1 alpha CD13 R [regular] condensing gas boiler , flue and connections</p> <p>to fit boiler to wall and run flow , return and gas to boiler</p> <p>to run control cables to clock , room stat , cylinder stat , diverter valve and boiler fitting of thermo radiator valves</p> <p>to flush system with cleaner filter unit , refill , vent run up and test install system saver</p> <p>to run condensate to lime chip filled drain soak away [this will involve digging a hole 700mm and fitting 1 gully grid onto 4" waste pipe and back fill with lime stones]</p> <p>to flush system with sentinel cleaner and filter unit , fill up , vent off and test for leaks</p> <p>to commission boiler to makers requirements , gas rate , temp of flow and return materials required pipe , fittings , connectors , valves , clips , fixings , sand and cement</p> <p>electrical goods required , clock , room stat , zone valves , 1 cylinder stat and 1 pump boiler unit is "A" rated and comes with extended guarantee if required</p> <p>on completion the boiler will be registered with CORGI and the local council a certificate will be sent to you from CORGI normally with in 20 days</p> <p>Electrical work will be completed by an NICELC registered engineer</p>			£0.00